## **TEMPORARY TRAFFIC CONTROL SIGNS - Item No.**

Special Provision No. 706S06

DRAFT October 2025

## Amendment to OPSS 706, November 2016 - Temporary Traffic Control Staging

## 706.03 DEFINITIONS

Section 706.03 of OPSS 706 is amended by deleting the definition for **Temporary Traffic Control Signs** in its entirety and replacing it with:

**Temporary Traffic Control Signs** means all traffic control signs and associated devices identified in OTM Book 7, including vehicles and sign trailers required to support signs and equipment to illuminate signs; but excludes highway number markers.

706.07 CONSTRUCTION

706.07.01 Temporary Traffic Control Signs

Subsection 706.07.01 title of OPSS 706 is deleted in its entirety and replaced with the following:

706.07.01 Temporary Traffic Control Staging

706.07.01.01 General

Clause 706.07.01.01 of OPSS 706 is amended by deleting bullet a) in its entirety and replacing it with the following:

a) Installation and relocation of temporary traffic control signs related to long-duration traffic control, as defined by OTM Book 7, unless otherwise specified in the Contract Documents.

Clause 706.07.01.01 of OPSS 706 is amended by deleting the eighth paragraph in its entirety and replacing it with the following:

Temporary traffic control signs shall be installed before work affecting traffic begins, remain operational throughout the duration of the long-duration work requiring temporary traffic control signs and be removed upon completion of the stage.

WARRANT: Always with this tender item.